

ADVERTISEMENT FOR BIDS

The City of Fort Pierre in Fort Pierre, South Dakota, will receive FIRM sealed bids at the City of Fort Pierre, P.O. Box 700, 08 E 2nd Ave, Fort Pierre, South Dakota, 57532, up to 3:00 PM CT, Wednesday, March 15, 2023, to complete **“2023 CRACK SEALING AND JOINT SEALING”** for the City of Fort Pierre.

Plans and Specifications are on file at the City Office and available at no cost.

The City of Fort Pierre reserves the right to accept or reject any or all BIDS, to waive any informality in the BID received and to accept the BID that is to the advantage of, and in the best interest of the City of Fort Pierre.

Each bid must contain a certified check, a Cashier's check or Draft, for five percent (5%) of the amount of the bid; such check to be certified or issued by either a State or National Bank and payable to the City of Fort Pierre or in lieu thereof a Bid Bond for Ten percent (10%) of the amount of this bid, such bond to be issued by a Surety authorized to do business in the State of South Dakota and payable to the City of Fort Pierre as a guarantee that such bidder will enter into a contract with said the City of Fort Pierre, thereof in accordance with the terms of such letting and bid in case such bidder is awarded the contract. The Certified Check or other guarantee, or bid bond of the successful bidder, will be returned to him forthwith upon the execution of the contract and surety hereafter provided for. The Contractor shall also provide proof of liability insurance and workman's compensation insurance.

Bids shall be marked **“2023 CRACK SEALING AND JOINT SEALING”** and sealed. The City of Fort Pierre requests one (1) Original Bid and one (1) copy. Bids may be mailed to the City of Fort Pierre, P.O. Box 700, Fort Pierre, South Dakota, 57532 or hand delivered to the Office of the Finance Officer, 08 East 2nd Ave., Fort Pierre, South Dakota 57532.

By order of the City of Fort Pierre City Council, dated this 6th day of February, 2023.

Roxanne Heezen, City Finance Officer

Advertisement published _____ and _____, 2023.

SPECIFICATIONS FOR 2023 CRACK SEALING AND JOINT SEALING

Base Project: Crack Sealing of approximately 146,460 SY of Asphalt Surfaced Streets in the City of Fort Pierre.

Alternate Project: Joint Sealing 12,790 SY of Concrete Surfaced Streets in the City of Fort Pierre.

The successful bidder is to furnish and install the Crack Sealant and Joint Sealant in accordance with the SDDOT standard Specifications with exceptions noted.

Base Project:

Contractor will be responsible clean, dry and prepare the cracks to receive the sealant.

Contractor is responsible for furnishing and installing the sealant.

Contractor will be responsible for all equipment, signing, brooming, pilot car, etc. to complete the Crack Sealing.

Contractor is responsible for brooming streets of routing and cleaning debris prior to opening streets to traffic.

Contractor shall provide copies of Insurance and Worker Compensation.

The SD DOT 2015 Standard specifications Section 350 will be used as a guideline for placement and material specifications. Section 871 shall apply to contractor furnished materials.

Modifications to SDDOT Standard Specifications are as follows:

Routing of Cracks less than 1/2" shall be routed to a width of 1/2" and depth of 3/4". Cracks greater than 1/2" shall not be routed.

Cracks between asphalt surfacing and concrete curb, driveway or concrete pavements shall be cleaned and sealed as specified.

Seasonal limitations revised to: Routing and Crack sealing of Asphalt concrete surfaces will be permitted only during daylight hours between January 1 and June 1, when air temperature is above 40 Degrees Fahrenheit and no precipitation anticipated for 48 hours after application of sealant.

The quantity includes streets to receive asphalt surface treatment in 2023 and other streets to be only crack sealed. Streets receiving Asphalt Surface Treatment in 2023 shall be completed first then other streets listed.

Final streets will be determined, and final price adjusted prior to issuance of the contract, information will be provided by City, and contractors will agree to all terms and conditions set forth by the City.

Base Project Work to be completed by June 1, 2023. Liquidated Damages of \$250 per day may be assessed.

Alternate Project:

Contractor will be responsible clean, dry and prepare the Joints to receive the sealant. Joints between curb and pavement are to be sealed.

Contractor is responsible for furnishing and installing the sealant.

Contractor will be responsible for all equipment, signing, brooming, pilot car, etc. to complete the Joint Sealing.

Contractor is responsible for brooming streets of cleaning debris prior to opening streets to traffic.

Contractor shall provide copies of Insurance and Worker Compensation.

The SD DOT 2015 Standard specifications Section 380 will be used as a guideline for placement and material specifications. Section 870 shall apply to contractor furnished materials.

Final quantities will be determined prior to issuance of the contract, information will be provided by City, and contractors will agree to all terms and conditions set forth by the City.

Alternate Project Work to be completed by October 1, 2023. Liquidated Damages of \$250 per day may be assessed.

The crack sealing and joint sealing will be applied at various locations around the city of Fort Pierre. Attached is a list and a map of the streets expected to receive crack sealing and joint sealing at time of the bid. Final locations for work will be determined prior to issuance of the contract.

Base Project Bid Unit Prices:

Price per Pound of Sealant \$ _____ per pound

Alternate Project Bid Unit Prices:

Hot Poured Elastic Joint Sealant \$_____ per Linear Foot

Low Modulus Silicone Sealant \$ _____ per Linear Foot

The unit prices above includes cleaning, routing, installing the sealants and incidental items necessary to complete the work as required.

Bidder is aware the City reserves the right to reduce or limit the project scope as work.

The Bidder is aware that Owner has the right to select any combination of projects or may elect to reject all bids.

Respectfully submitted by: _____

Signature: _____

Address: _____

Title: _____

City, State, Zip: _____

Date: _____

License Number (If Applicable)

(SEAL * If BID is by a Corporation)

ATTEST

2023 Fort Pierre Asphalt Surface Treatment Streets

Asphalt Surfacing

Street_Name	Work	Width	Length	Area (SY)	Comments
7th Ave E 200-400 Block & CDS	Single Application	44	210	1,027	CDS
2nd St S - 500-600 Blk	Single Application	40	675	3,000	
7th St N - 200 Block	Double Application	30	375	1,250	Follow reconstruction project
Caol Ila Ct	Single Application	40	650	2,889	CDS
Port Na Haven - 1600-1700 Blk	Single Application	40	800	3,556	
Cottonwood Lane 300 Block	Single Application	35	300	1,167	Straight Thru CDS
Cottonwood Lane - 200 Block	Double Application	24	480	1,280	New Surface over Granular Base
Islay Ave E - 100-200 Blk	Single Application	40	1210	5,378	Stop before CDS
Marion St - 500-600 Blk	Single Application	40	590	2,622	CDS
Park Ave E - 100-200 Blk	Single Application	36	740	2,960	
Park Ave W - 200-300 Blk	Single Application	36	720	2,880	Crossing Railroad
Stanley Rd E - 100 Blk	Single Application	52	570	3,293	
Scotty Philip Ave - 100-400 Blk	Single Application	40	1350	6,000	
Wandel E - 200 Blk	Single Application	40	375	1,667	
Rowe Ln	Single Application	30	500	1,667	
2nd Ave -10 Blk	Single Application	50	600	3,333	
Royal Ct - 1400 blk	Single Application	40	600	2,667	
La Framboise Dr - 400 Blk	Single Application	40	360	1,600	

Total Area	48,236 SY
-------------------	------------------

2023 Fort Pierre Crack Seal and Joint Seal Streets Only

Crack Sealing & Joint Sealing

Street_Name	Work	Width	Length	Area (SY)	Comments
1st Ave W 100-600 Blk	Crack Sealing	45	2250	11,250	CDS
3rd St -N & S 100 Blks	Crack Sealing	40	875	3,889	
9th Ave E - 100-300 Blk	Crack Sealing	28	1530	4,760	
Beach Drive - Islay CDS	Crack Sealing	42	615	2,870	
Dakota Ave	Crack Sealing	42	790	3,687	
Deadwood St - 100 500 Blk	Crack Sealing	48	2275	12,133	
Fort Chouteau Rd	Crack Sealing	30	2120	7,067	
Main Ave E 100-300 Blk and W 100-400 Blk	Crack Sealing	50	2950	16,389	CDS East End
Lindsay Tr	Crack Sealing	42	1075	5,017	
Marion St - 700 Blk	Crack Sealing	40	360	1,600	
Marina Dr Parking Lot	Crack Sealing	200	200	4,444	
Park Ave W - 100 Blk	Crack Sealing	36	360	1,440	
Pheba Ave E 100-200 Blk & W 100-200 Blk	Crack Sealing	40	1290	5,733	
Rose Lane	Crack Sealing	36	330	1,320	CDS
Telegraph Tr	Crack Sealing	40	900	4,000	
Tiree Dr	Crack Sealing	40	950	4,222	
Waldron N - 1900-2200 Blk	Crack Sealing	45	1680	8,400	
La Framboise Dr - 600-1000 Blk	Joint Sealing	42	1560	7,280	
Casey Tibbs Street - 600-700 Blk	Joint Sealing	40	740	3,289	
Two Rivers	Joint Sealing	40	500	2,222	

Crack Sealing Only Total	98,221 SY
--------------------------	-----------

Joint Sealing Only Total	12,791 SY
--------------------------	-----------

Crack Sealing Total	146,457 SY
---------------------	------------

Joint Sealing Total	12,791 SY
---------------------	-----------